

Capital Improvement Projects Fall / Winter

Caseyville Public Works Department 2021/2022

North Long Street Pavement Overlay

The project consists of furnishing all labor, materials, and equipment required for approximately 1/3-mile of road re-surfacing with a HMA leveling binder and a 2-inch HMA surface course, butt joints, and incidentals. The reconstruction will reconstruct the current oil and chip road into an asphalt pavement. Some of the shoulders will remain chip and sealed. Installing new culverts as needed, cleaning and flushing ditches and culverts. Street will be open to local traffic only during construction. The work is scheduled to be completed in the 2021 paving season.

South Long Street Pavement Overlay

The proposed work consists of approximately 1.1-miles of street re-surfacing with a HMA leveling binder and a 2-inch HMA surface course, butt joints, and incidentals. The reconstruction will reconstruct the current oil and chip road into an asphalt pavement. Some of the shoulders will remain chip and sealed. All side streets from Long Street to Highway 157 will be overlaid with the project. Installing new culverts as needed, cleaning and flushing ditches and culverts. Street will be open to local traffic only during construction. The work is scheduled to be completed in the 2021 paving season.

Hollywood Heights Road Water Line Improvements

Caseyville Water Department crews will be working on the 2nd phase of the Hollywood Heights Road watermain replacement. Project consist of installing pressure sustaining valves, new fire hydrants, and a new 8" watermain. Construction area will be on Hollywood Heights Road, between Hillside Drive and Oliver Street.

West Mill Creek Road Water Line Improvements

Project consist of replacing approximately 500' of 6" watermain along Mill Creek and East Mill Creek bridge in Troy, IL, that is scheduled for demo and replacement. Caseyville Water department crews will be working with Madison County Highway department during this construction.

Caseyville Water Elevated Tower

Elevated Water tank located at 9 Pines Road, O'Fallon, IL will be drained and inspected. Cleaning of tank and repairs will be addressed based on the findings of the tank inspection. Tank mixing valves and pumps will be installed. After cleaning and repairs, the tank will be disinfected by chlorination.